



PORTER HOSPITAL FAST FACTS

SCHEDULE

- Ground Breaking was June 24, 2010
- Steel Erection commenced October 18, 2010
- Topping Out Ceremony on March 18, 2011
- Exterior Skin Substantial Completion September 1, 2011
- Substantial Completion will be before July 1, 2012 (approximately 3 months early)

OCCUPANCY

- 225 Beds
- 10 Operating Rooms (including Open Heart & Cysto OR Rooms)
- 2 Future Operating Rooms
- Emergency Department:
 - 3 Trauma Rooms
 - 3 Cardiac Rooms
 - 24 Exam Rooms
 - 2 Triage Rooms
- Fully Equipped Imaging Department:
 - 1 MRI Room
 - 4 Cath Labs
 - 2 Future Cath Labs
 - 3 Nuclear Medicine Rooms
 - 2 CT Scan Rooms
 - 1 Mammo
 - 3 Ultrasound Rooms
 - 4 X-Ray Rooms
 - 1 Specialty Procedures
 - 1 Bone Density

LANDSCAPE

- 2,100 Plants (Shrubs & Perennials)
- 536 Trees
- 14 acres of Sod & Seeding
- Pocket Park with Fountain
- 3 Flag Poles

STRUCTURE

- 459,145 SF Building
- Over 1,300 Vibro Stone Columns (Aggregate Piers)
- 389 tons of Reinforcing Steel Rebar
- Approximately 11,500 CY concrete
- 2,400 tons of Structural Steel
- 434,500 SF Metal Decking

SITE

- 104 acre heavily wooded site
- 40 acres cleared & developed
- Building footprint & paved surfaces is 22 acres
- Cut/Fill 121,500 CY of dirt
- 9,080 LF of Storm Water piping (1.72 miles)
- 17,062 LF of Water/Sewer/Fire piping (3.23 miles)
- 12,937 LF Concrete Curb
- 30,342 SF Concrete Paving
- 566,685 SF Asphalt Paving



PORTER HOSPITAL FAST FACTS

EXTERIOR MATERIALS

- 135,000 SF Sheathing
- 245,000 LF Exterior Framing (46 miles)
- 163,000 SF Insulation
- 21,560 SF Exterior Glass
- 110,000 SF of EIFS
- 77,000 SF of Brick & Block
- 141,500 SF EPDM Roof Membrane System
- 8 each Bi-Parting Automatic Sliding Door

INTERIOR MATERIALS

- 1,030,000 LF Interior Framing (195 miles)
- 1,700,000 SF Gypsum Board
- 90-100 Truck Loads of Gypsum Board
- 310,000 SF Acoustical Ceiling Tile
- 20,000 bags Sprayed Fireproofing
- 1,475 Hollow Metal Door Frames
- 1,587 Doors (Plastic Laminate & Hollow Metal)
- 29 Lead Lined Plastic Laminate Doors
- 1,692 Hardware Locksets
- 54 each Automatic Door Swing Operators
- 47 each Bi-Way ICU Breakout Doors
- 29,000 SF of Hard Tile
- 218,726 SF VCT & Vinyl Tile Flooring
- 7,950 SY Sheet Vinyl Flooring (71,550 SF)
- 8,460 SY Carpet (76,140 SF)
- 5,815 LF of Plastic Laminate Cabinets
- 6,698 LF of Countertops/Worktops
- 1,550 Corner Guards
- 4,722 LF of Wall Protection Sheet Goods (18,888 SF)
- 8,300 LF of Handrail & Crashrail
- 4,800 LF Cubicle Curtain Track
- 1,364 Metal Lockers
- 170 Amico Recessed Headwall Units
- 38 Ceiling Mounted Surgical/Exam Lights
- 15 Sterilizers
- 112 Refrigerators
- 15 Ice Machines
- 39 Microwaves

MECHANICAL

- 3 – 400 HP Boilers
- 3 – 725 ton Chillers
- 3 Cooling Towers
- 1 – 60 ton Air Cooled Data Room Chiller
- 657 each VAV's
- 36 Hydronic Pumps
- 55 Exhaust fans
- 14 Air Handler Units
- 7 Roof Top Air Handler Units
- 550,000 Pounds of Sheet Metal HVAC Duct
- 3,500 Grilles & Diffusers
- Approximately 67 miles of Plumbing, Heating & Medical Gas Piping
- 3,500 Sprinkler Heads & 40 Hose Valve Cabinets



ELECTRICAL

- 3 – 1000 kw Emergency Generators
- 610,000 LF Conduit
- 3,140,000 LF of Electrical Wire
- 6,405 Electrical Receptacles
- 2,980 Electrical Switches
- 7,610 Light Fixtures



G R E S H A M
S M I T H A N D
P A R T N E R S

ROBINS & MORTON